FIO Committee Presentation, Nov 9, 2026: graded copy

Original PPS slides (BoardBook document 14644366), unchanged. Red marks and margin notes check the slides against PPS's own rules (p.6), its Nov 2 capacity model, its April 2026 enrollment and utilization table, the family guides, and 2015-16 enrollment records.

p.19	Hayhurst: "640" is wrong (396; building max 499 in 2015); 7 special-ed rooms vs 4 on the same page and 3 in the model; model rules give 516	-9
p.33	Seismic: B worse than status quo on 9.0+ buildings; "reduction" is mostly bond retrofits; URM gain rests on unscheduled proposed projects	-10
p.27	Sitton rated "Ready" at 111% of capacity	-5
p.29	Whitman rated "Ready" at 112% of capacity; 1 vs 4-5 special-ed rooms	-5
p.5	"21 buildings with the highest increase" leaves out Harrison Park, Tubman, Lent, Rieke, Roseway Heights	-4
p.26	Rosa Parks: 3 special-ed rooms counted vs 6-7 needed; capacity cut from 633 to 499 unexplained	-4
p.21	Markham: capacity raised 510 -> 561; Maplewood ISC students into a "Not Yet Ready" building	-3
p.31	Rieke gets seismic money but no readiness profile	-3
p.13 / 16 / 28	Capacity raised since April at Capitol Hill, Duniway, Vestal (over 100% under April figures)	-6
p.17 / 20	George, Hosford: more special-ed rooms than the capacity model sets aside	-4
p.30	"All campuses ADA accessible to the main floor" understates access problems	-2
p.22-29	Hidden leftover text from other slides	-1



Please show your work. The capacity numbers on these slides do not follow from the room counts on the same slides.

Sources and full analysis: github.com/timaelliott/save-our-schools, analysis/meetings/2026-11-09_fio_materials.md. Prepared Nov 6, 2026 from PPS public records.

FIO Committee

November 9, 2026



PORTLAND
Public Schools

Agenda

- Welcome and Introductions
- Departmental Wins
- School Readiness Assessment Process and Districtwide Findings
- School by School Review
- Confirming Receiving School Readiness
- Next Steps

Departmental Wins

RISE

Bond Program Wins!

- Ida B Wells Land Use Approval received!
- Grice-Adair had 6 CM/GC firm submit proposals which is twice the historical numbers of participants in response to CM/GC.
- All roofing projects are in close-out including Vestal, Chavez, Marshall (phase1) and Woodmere.
- Beverly Cleary Seismic Retrofit in for permit and contractor RFP issued
- Richmond, Ainsworth and Kelly Seismic Retrofit - contractor RFP schedule before mid-Dec

Purpose

Review School Readiness for potential receiving schools from a facilities and operations lens.

Today we will:

a. Review our process for determining facilities readiness

b. Walk through facilities readiness of schools receiving the highest number of students

c. Model scenario A and B. Discuss what a potential seismic plan would look like

Assessing Facilities Readiness Process

- When initially assessing a school's readiness to welcome students we looked at a building's functional capacity, the current utilization rate, and the number of work orders received from each building.

- We utilized our data from our facilities teams, and pulled data from Tririga, which shows the number of classrooms currently being used for what purpose.

- In June, we brought principals in to look at their school's floor plan and provide feedback on how they are using their spaces.

- When scenarios were released, operations teams comprised of facilities, maintenance, RISE, safety and security, nutrition, and transportation did in-person walkthroughs with principals of 21 buildings set to experience the highest number of student increase. 1

-4

1 Not the 21 biggest increases. Missing: Harrison Park +215, Tubman +151, Lent +147, Rieke +117, Roseway Heights +116. Included: Capitol Hill +68, Ockley Green +110. (Peak vs. no-change projection, PPS family guides.)

Functional Capacity: Planning Assumptions

The PPS Utilization Model estimates student capacity using classroom size, space set-asides, and school scheduling needs.

- **Classroom capacity:** Classrooms must be at least 500 sq. ft. Estimated capacity is:
  a. **24 students** for 500–800 sq. ft.;
  b. **27 students** for 801–1,000 sq. ft.;
  c. **30 students** for larger classrooms.
  d. These are planning assumptions, not class-size minimums or maximums.
- **Enrichments and Electives:**
  a. K–5/K–8 calculations exclude gymnasiums and one or two Art/Music rooms, based on enrollment.
  b. Middle/high school calculations use lower utilization assumptions to account for rotating schedules and specialized instructional spaces.
- **Special Education classrooms are intentionally protected:**
  a. Special Education classrooms are set aside from general instructional functional capacity, so they are not assumed to be available for other classroom uses.
  b. Model includes specialized program classroom(s) and Learning Centers (in K-5/K-8).
  c. Classrooms used for students who receive specialized instruction for most of the school day. Capacity in these rooms is 12 students.

***Actual Space Use:** Capacity reflects how spaces could support instruction. Principals determine actual space use (room assignments and any necessary changes).

OK

1 Noted: special-ed rooms count 12 students.

2 Noted: 24 / 27 / 30 per room by size; one art/music room comes out at K-5. We use these rules to check p.19 and p.26.

Campus Readiness Profiles by School

Readiness Status

- Not Yet Ready/ Significant Barriers
- Conditionally Ready/ Improvements Needed
- Ready/ Minor Adjustments

Campus Readiness Profile

[Campus Name]

Readiness Status

- Not Yet Ready/ Significant Barriers
- Conditionally Ready/ Improvements Needed
- Ready/ Minor Adjustments

Capacity at a Glance

FUNCTIONAL CAPACITY

[000] students

PEAK ENROLLMENT

[000] students in [Year]

LARGEST HISTORIC ENROLLMENT

[000] students in [Year]

CLASSROOM USE

[00] SPED classrooms
[00] total classrooms

Planned Future Investments

[A,B,C,D.E]

Readiness for Additional Students

- Urgent improvement:
  - [Improvement] [Target timing / next decision point, estimated cost implication]
- Needed improvement that does not affect school readiness
  - [Improvement]
- Accessibility: ## Accessible classrooms.
  - [Additional accessibility info]

Safety & Security

- [Brief safety/security impact, constraint, or no notable issue]

Nutrition Services

- [Brief kitchen, meal-service, or space requirement]

Transportation

- [Brief transportation impact, constraint, or no notable issue]

Special Education

- [Brief program, space, access, or service consideration]

Campus Readiness Profile

Abernethy

Readiness Status: Ready/ Minor Adjustments

Capacity at a Glance

FUNCTIONAL CAPACITY

441 students

PEAK ENROLLMENT

369 students in 2029

LARGEST HISTORIC ENROLLMENT

528 students in 2013-2014

CLASSROOM USE

1 SPED classroom
21 classrooms

Planned Future Investments

None at this time

Readiness for Additional Students

- Urgent improvement:
  - Nutrition Services additions for kitchens, see below:
    - $38,300 - completed by Summer 2027
  - Additional WiFi Coverage
- Needed improvement that does not affect school readiness
  - Resolve groundwater issues in Rm 4 - $100K
- Accessibility: 11 Accessible classrooms.
  - First floor accessible; accessed on NW side of building
  - Does not have an elevator

Safety & Security

- Fencing
- Additional cameras to address blind spots

Nutrition Services

- Additional double oven, double door freezer and warming oven ($38,300)

Transportation

- City review and expansion required. Space available. No notable issues.

Special Education

- One Learning Center
- 1 Classroom Total

Campus Readiness Profile

Arleta

Readiness Status: Ready/ Minor Adjustments

Capacity at a Glance

FUNCTIONAL CAPACITY
653 students

PEAK ENROLLMENT
552 students In 2030

LARGEST HISTORIC ENROLLMENT
526 students in 2019-2020

CLASSROOM USE

4 SPED classrooms
26 classrooms

Planned Future Investments

PCEF Mech Upgrades

Readiness for Additional Students

- Urgent improvement:
  - Nutrition Services additions for kitchens, see below:
    - $30,100 - completed by Summer 2027
  - Increase railing height at stairwells
- Needed improvement that does not affect school readiness: None
- Accessibility: 19 Accessible classrooms.
  - First floor accessible; accessed on NW side of building
  - Does not have an elevator

Safety & Security

- Fencing

Nutrition Services

- Additional double oven and warming cabinet ($30,100)

Transportation

- City review and expansion required. Space available.
- No notable issues.

Special Education

- Continue Social Emotional Skills programming for students in grades 3–5.
- Welcoming students from Marysville K-5 Inclusive School Community
- 1 regulation/sensory space
- 4-5 Classrooms Total

Campus Readiness Profile

Boise-Eliot/Humboldt

Readiness Status: Ready/ Minor Adjustments

Capacity at a Glance

FUNCTIONAL CAPACITY
586 students

PEAK ENROLLMENT
540 students in 2028

LARGEST HISTORIC ENROLLMENT
696 students in 1999-2000

CLASSROOM USE

4 SPED classrooms
31 classrooms

Planned Future Investments

DLCD Grant Vision Plan

Readiness for Additional Students

- Urgent improvement: None
- Needed improvement that does not affect school readiness:
  - Vinyl windows need to be addressed (loose and unsafe - cost TBD)
- Accessibility: 20 Accessible classrooms.
  - First floor accessible
  - Does not have an elevator

Safety & Security

- Fencing
- Additional cameras to address camera blind spot areas

Nutrition Services

- Ready

Transportation

Current space is adequate. No notable issues.

Special Education

- BEH has 1.5 Learning Center FTE
- 2 Communication Behavior Classrooms
- 1 Sensory/Regulation space
- 4-5 Classrooms Total

Campus Readiness Profile

Brentwood

Readiness Status: Ready/ Minor Adjustments

Capacity at a Glance

FUNCTIONAL CAPACITY
763 students

PEAK ENROLLMENT
664 students In 2028

LARGEST HISTORIC ENROLLMENT
770 students in 1997-1998

CLASSROOM USE

4 SPED classrooms
35 classrooms

Planned Future Investments

DLCD Grant Vision Plan

Readiness for Additional Students

- Urgent improvement: None
- Needed improvement that does not affect school readiness
  - Lockers, cameras, outdoor space upgrades, repair gymnasium operable partition
- Accessibility: 24 Accessible classrooms.
  - First floor accessible
  - Does not have an elevator

Safety & Security

- Fencing
- Door locks & access control
- Additional cameras to address blind spots

Nutrition Services

- Ready

Transportation

City review and expansion required. Possible space issues.

Special Education

- 2.5 Learning Center Teachers
- 1 ISC Classroom and 1 SES Classroom
- 1 Sensory/Regulation Space
- 4 Classrooms Total

Campus Readiness Profile

Capitol Hill

Readiness Status: Ready/ Minor Adjustments

Capacity at a Glance

FUNCTIONAL CAPACITY 1
417 students

PEAK ENROLLMENT
387 students in 2030

LARGEST HISTORIC ENROLLMENT
460 students In 2014-2015

CLASSROOM USE
2 SPED classrooms
17 classrooms

Planned Future Investments
Seismic Retrofit

Readiness for Additional Students

- Urgent improvement:
  - Nutrition Services additions for kitchens, see below:
    - $80,100 - completed by Summer 2027
- Needed improvement that does not affect school readiness:
  - Portables need new siding (Cost: TBD)
- Accessibility: 15 Accessible classrooms.
  - First floor accessible
  - Does not have an elevator

Safety & Security

- Access control (additional exterior card readers)

Nutrition Services

- Additional double ovens, new dishwasher, Warming cabinet ($80,100)

Transportation

City review and expansion required. Space available. No notable issues.

Special Education

- 1 Learning Center Teacher
- 1 Classroom Total

-2

1 Capitol Hill was 375 in PPS's April 2026 table. At 375, the 387 peak is 103%. The +42 is not explained.

Campus Readiness Profile

César Chávez

Readiness Status: Ready/ Minor Adjustments

Capacity at a Glance

FUNCTIONAL CAPACITY
564 students

PEAK ENROLLMENT
541 students in 2027

LARGEST HISTORIC ENROLLMENT
587 students in in 2007-2008

CLASSROOM USE

2 SPED classrooms
29 classrooms

Planned Future Investments

PCEF Comfort/Climate Upgrades
PCEF Schoolyard Upgrade
Covered Play Structure

Readiness for Additional Students

- Urgent improvement:
  - Nutrition Services additionals for kitchens (see below):
    - $3,100 - completed by Summer 2027
- Needed improvement that does not affect school readiness
  - Needs AV upgrades (check with IT)
- Accessibility: 31 Accessible classrooms.
  - Has elevator and full ADA access.
  - Needs some minor work in restrooms

Safety & Security

- Fencing

Nutrition Services

- Warming cabinet ($3,100)

Transportation

- City review and expansion required. Space available. No notable issues.

Special Education

- Inclusive School Community
- 2.5 Special Education Teachers
- 3 Classrooms Total

Campus Readiness Profile

Chief Joseph

Readiness Status: Ready/ Minor Adjustments

Capacity at a Glance

FUNCTIONAL CAPACITY
444 students

PEAK ENROLLMENT
426 students In 2028

LARGEST HISTORIC ENROLLMENT
481 students in 2011-2012

CLASSROOM USE

1 SPED classrooms
18 classrooms

Planned Future Investments

None

Readiness for Additional Students

- Urgent improvement:
  - No projectors in portables - completed by Summer 2027
  - Nutrition Services additions for kitchens (see below):
    - $3,100 - completed by Summer 2027
- Needed improvement that does not affect school readiness: None
- Accessibility: 15 Accessible classrooms.
  - First floor accessible
  - Does not have an elevator

Safety & Security

- Fencing
- Additional Cameras-Cafeteria

Nutrition Services

- Warming Cabinet ($3,100)

Transportation

- City review and expansion required. Space available. No notable issues.

Special Education

- 1 Learning Center Teacher
- 1 Classroom Total

Campus Readiness Profile

Duniway

Readiness Status: Ready/ Minor Adjustments

Capacity at a Glance

FUNCTIONAL CAPACITY
552 students

PEAK ENROLLMENT
544 students In 2027

LARGEST HISTORIC ENROLLMENT
512 students in 2019-2020

CLASSROOM USE

1 SPED classrooms
24 classrooms

Planned Future Investments

None

Readiness for Additional Students

- Urgent improvement:
  - Nutrition Services additions for kitchen (see below):
    - $83,000 - completed by Summer 2027
- Needed improvement that does not affect school readiness: None
- Accessibility: 16 Accessible classrooms.
  - First floor accessible
  - Does not have an elevator

Safety & Security

- Fencing/Gates
- Additional doors on access control

Nutrition Services

- Double ovens, Dishwasher, Warming Cooler, Milk Cooler ($83,000)

Transportation

- City review and expansion required. Space available. No notable issues.

Special Education

- 1 Learning Center Teacher
- 1 Classroom Total

-2

1. Was 525 in April. At 525 the peak is 104%.
2. Peak 544...
3. ...is more than the most students Duniway has ever had (512).

Campus Readiness Profile

George

Readiness Status: Not Yet Ready/ Significant Barriers

Capacity at a Glance

FUNCTIONAL CAPACITY
623 students

PEAK ENROLLMENT
669 students In 2029

LARGEST HISTORIC ENROLLMENT
588 students in 1996-1997

CLASSROOM USE
7 SPED classrooms
26 classrooms

Planned Future Investments

DLCD Grant Vision Plan
Covered Play Structure

Readiness for Additional Students

- Urgent improvement:
  - Nutrition Services additions for kitchen (see below)
    - $15,000 - completed by Summer 2027
  - Additional space for PE - Outdoor covered Structure $750K (Summer 2028)
- Needed improvement that does not affect school readiness: None
- Accessibility: 33 Accessible classrooms.
  - Full access to building.

Safety & Security

- Fencing/Gates
- Additional access controlled doors
- Additional cameras to address camera blind spots

Nutrition Services

- Milk Cooler, Warming Cabinet ($15,000)

Transportation

- City review and expansion required. Space available. No notable issues.

Special Education

- 3 Learning Center Teachers
- 1 SES Classroom and 2 ISC classrooms
- 1 Sensory or regulation space
- 7 Classrooms Total

-2

1 *7 special-ed rooms here, but PPS's capacity model sets aside only 3. Capacity (623) was not reduced, so it is too high. Peak 669 is already 107%.*

Campus Readiness Profile

Gray

Readiness Status: Ready/ Minor Adjustments

Capacity at a Glance

FUNCTIONAL CAPACITY
588 students

PEAK ENROLLMENT
551 students in 2029

LARGEST HISTORIC ENROLLMENT
566 students in 2015-2016

CLASSROOM USE

3 SPED classrooms
23 classrooms

Planned Future Investments

None

Readiness for Additional Students

- Urgent improvement:
  - Nutrition Services kitchen additions (see below)
    - $30,100 - completed by Summer 2027
- Needed improvement that does not affect school readiness
  - Restrooms in band area need to be returned to restrooms (not storage), upper floor lockers need locks replaced (cost: TBD)
- Accessibility: 23 Accessible classrooms.
  - A stair lift provides access to lower levels, though the building's size and layout make the accessible route indirect and difficult to navigate.

Safety & Security

- Additional cameras to address blind spots

Nutrition Services

- Double ovens, warming cabinet ($30,100)

Transportation

- City review and expansion required. Space available. No notable issues.

Special Education

- 2 Learning Center Teachers
- 1 SES Classroom
- 1 Sensory or regulation space
- 4 Classrooms Total

Campus Readiness Profile

Hayhurst

Readiness Status: Ready/ Minor Adjustments (5)

Capacity at a Glance

FUNCTIONAL CAPACITY (2)

525 students

PEAK ENROLLMENT

469 students in 2027 (4)

LARGEST HISTORIC ENROLLMENT (1)

~~640~~ students in 2019-2020

CLASSROOM USE (3)

7 SPED classrooms
15 classrooms

Planned Future Investments

None

Readiness for Additional Students

- Urgent improvement:
  - Nutrition Services additions for kitchen (see below)
    - $30,100 - completed by Summer 2027
- Needed improvement that does not affect school readiness
  - Old windows should be replaced, parking lot restriping
- Accessibility: 23 Accessible classrooms.
  - Full access to building.

Safety & Security

- Additional cameras to address blind spots

Nutrition Services

- Double ovens, Warming cabinet ($30,100)

Transportation

- City review and expansion required. On property adjustments required and able to accommodate.

Special Education

- Continue one Learning Center and two Social Emotional Skills classrooms.
- 1 Sensory or regulation space
- 4 Classrooms Total (6)

-9

1. Wrong. PPS's own capacity model lists Hayhurst at 396 in 2019-20. The 640 adds Odyssey (244), which moved to East Sylvan in 2016. Most ever in this building: 499 in fall 2015.
2. 525 matches PPS's Nov 2 model: 20 rooms x 27 + 2 x 30 + gym 30 = 630, minus 5 set-aside rooms = 525. But the model takes the gym out at 27, not 30, and leaves 15 seats in each special-ed room (its rule says 12). By its own rules: 516.
3. The model sets aside 2 special-ed rooms + a Learning Center, not 7. If 7 is right, capacity is about 468.
4. 469 = 89% of 525, 91% of 516. In 2016, PPS's figures put a K-5-only Hayhurst at about 464 seats (327 students = 70.6%).
5. "Ready"? In 2016 PPS called 499 students here "Over-Crowding" (101.8%) and moved a whole program out.
6. This box says 4 special-ed rooms; the left panel says 7. Which is it?

Campus Readiness Profile

Hosford

Readiness Status: Conditionally Ready/ Improvements Needed

Capacity at a Glance

FUNCTIONAL CAPACITY

711 students

PEAK ENROLLMENT

747 students in 2028

LARGEST HISTORIC ENROLLMENT

676 students in 2020-2021

CLASSROOM USE

5 SPED classrooms
28 classrooms

Planned Future Investments

None

Readiness for Additional Students

- Urgent improvement:
  - Nutrition Services additions for kitchen (see below):
    - $30,100 - completed by Summer 2027
- Needed improvement that does not affect school readiness
  - As with most schools, needs some cosmetic improvements (paint, new carpet)
- Accessibility: 29 Accessible classrooms.
  - Has elevator for access to 1st and 2nd floors, .
  - Basement classrooms (4) are inaccessible or difficult to navigate to.

Safety & Security

- Additional cameras to address blind spots

Nutrition Services

- Double ovens, warming cabinet ($30,100)

Transportation

- City review and expansion required. Space is limited. Further discussion with the city is required.

Special Education

- 2 Learning Center Teachers
- 1 ISC Classroom
- 3 Classrooms Total

-2

1. 747 / 711 = 105%.
2. 5 special-ed rooms here...
3. ...3 here, and 1 in PPS's capacity model.

Campus Readiness Profile

Markham

Readiness Status: Not Yet Ready/ Significant Barriers

Capacity at a Glance

FUNCTIONAL CAPACITY 1
561 students

PEAK ENROLLMENT
554 students In 2030

LARGEST HISTORIC ENROLLMENT
456 students in 2017-2018

CLASSROOM USE
2 SPED classrooms
22 classrooms

Planned Future Investments
None

Readiness for Additional Students

- Urgent improvement:
  - Nutrition Services additions to kitchen (see below):
    - $80,100 - completed by Summer 2027
- Needed improvement that does not affect school readiness
  - Roof needs to be replaced (cost: TBD)
- Accessibility: 24 Accessible classrooms.
  - Full access to building.

Safety & Security

- Fencing
- Additional access controlled doors

Nutrition Services

- Double ovens, warming cabinet, dishwasher ($80,100)

Transportation

- Space constraints. Limited street frontage. Options around the building and traffic flow adjustments are required including traffic controls.

Special Education

- Students in Maplewood's Intensive Skills Classroom will return to Markham, with two total ISC classrooms and one Learning Center. 2
- 3 Classrooms Total

-3

1 Was 510 in April. At 510 the 554 peak is 109%. Peak is also above the most ever enrolled (456).

2 Maplewood's Intensive Skills students would move into a building rated "Not Yet Ready."

Campus Readiness Profile

Metropolitan Learning Center

Readiness Status: Ready/ Minor Adjustments

Capacity at a Glance

FUNCTIONAL CAPACITY
487 students

PEAK ENROLLMENT
421 students In 2027

LARGEST HISTORIC ENROLLMENT
490 students in 1997-1998

CLASSROOM USE

2 SPED classrooms
20 classrooms

Planned Future Investments

None

Readiness for Additional Students

- Urgent improvement:
  - Nutrition Services kitchen additions (see below):
    - $33,800 - completed by Summer 2027
- Needed improvement that does not affect school readiness
  - Exterior masonry work, all classroom hardwood floors need to be refinished, gym and locker room roof need to be addressed (costs: TBD)
- Accessibility: 22 Accessible classrooms.
  - Full access to building.

Safety & Security

- No safety/security concerns identified

Nutrition Services

- Double ovens, warming cabinet, milk cooler, additional prep table ($33,800)

Transportation

- Transportation not currently planned to MLC. Limited space is available for the future.

Special Education

- 2 Learning Center Teachers
- 2 Classrooms Total

-1

Hidden text from other slides sits under pages 22-29 (e.g. "561 students", "456 students in 2017-2018"). It is invisible here but is what screen readers and copy-paste pick up.

Campus Readiness Profile

Mt. Tabor

Readiness Status: Ready/ Minor Adjustments

Capacity at a Glance

FUNCTIONAL CAPACITY
752 students

PEAK ENROLLMENT
647 students In 2027

LARGEST HISTORIC ENROLLMENT
730 students in 2016-2017

CLASSROOM USE

3 SPED classrooms
32 classrooms

Planned Future Investments

None

Readiness for Additional Students

- Urgent improvement:
  - Nutrition Services kitchen additions (see below):
    - $30,100 - completed by Summer 2027
- Needed improvement that does not affect school readiness
  - Some window replacement, new carpet in a few spaces (cost: TBD)
- Accessibility: 35 Accessible classrooms.
  - Full access to building

Safety & Security

- Fencing

Nutrition Services

- Double ovens, warming cabinet ($30,100)

Transportation

- City review and expansion required. On property adjustments required and able to accommodate.

Special Education

- 1 Learning Center Teacher
- 1 ISC Classroom
- CRIS MS DHH Site
- 3 Classrooms Total

Campus Readiness Profile

Ockley Green

Readiness Status: Ready/ Minor Adjustments

Capacity at a Glance

FUNCTIONAL CAPACITY
657 students

PEAK ENROLLMENT
552 students In 2027

LARGEST HISTORIC ENROLLMENT
661 students in 1996-1997

CLASSROOM USE

4 SPED classrooms
35 classrooms

Planned Future Investments

DCLD Grant Vision Plan
Covered Play Structure

Readiness for Additional Students

- Urgent improvement:
  - Nutrition Services kitchen additions (see below):
    - $3,100 - completed by Summer 2027
- Needed improvement that does not affect school readiness
  - Boiler & burner upgrades, HVAC issues to be addressed, roof issues (cost: TBD)
- Accessibility: 23 Accessible classrooms.
  - Review ADA push button functionality.
  - First floor accessible
  - Does not have an elevator

Safety & Security

- Additional access controlled doors
- Additional cameras to address blind spots

Nutrition Services

- Warming cabinet ($3,100)

Transportation

- City review and expansion required. Space available. No notable issues.

Special Education

- 2 Learning Center Teachers
- 2 Classrooms Total

Campus Readiness Profile

Rigler

Readiness Status: Ready/ Minor Adjustments

Capacity at a Glance

FUNCTIONAL CAPACITY
621 students

PEAK ENROLLMENT
515 students In 2028

LARGEST HISTORIC ENROLLMENT
576 students in 1997-1998

CLASSROOM USE

1 SPED classrooms
27 classrooms

Planned Future Investments

None

Readiness for Additional Students

- Urgent improvement:
  - Nutrition Services kitchen additions (see below):
    - $3,100 - completed by Summer 2027
- Needed improvement that does not affect school readiness: None
- Accessibility: 22 Accessible classrooms.
  - Has elevator for full access to main building.

Safety & Security

- Fencing

Nutrition Services

- Warming Cabinet ($3,100) May need an additional cooler - cafeteria is incredibly tight and will need detailed scheduling with principal to accommodate.

Transportation

- City review and expansion required. Space available. No notable issues.

Special Education

- 1 Learning Center Teacher
- 1 Classroom Total

Campus Readiness Profile

Rosa Parks

Readiness Status: Ready/ Minor Adjustments

Capacity at a Glance

FUNCTIONAL CAPACITY

499 students (1)

PEAK ENROLLMENT

487 students In 2028

LARGEST HISTORIC ENROLLMENT

562 students in 2007-2008

CLASSROOM USE

3 SPED classrooms (2)

23 classrooms

Planned Future Investments

None

Readiness for Additional Students

- Urgent improvement:
  - Nutrition Services kitchen additions (see below)
    - $3,100 - completed by Summer 2027
- Needed improvement that does not affect school readiness
  - Vinyl flooring in restrooms needs to be addressed around toilets,
- Accessibility: 26 Accessible classrooms.
  - Has elevator for full access to building

Safety & Security

- No safety/security concerns identified

Nutrition Services

- Warming cabinet ($3,100)

Transportation

- City review and expansion required. Space available. No notable issues.

Special Education

- Inclusive School Community
- 5.5 Special Education Teachers
- 1 Regulation/Sensory Space
- Approximately 6-7 Classrooms (programming) (3)

-4

1. Was 633 in April. Now 499: the change is not explained.
2. 3 special-ed rooms counted...
3. ...but 6-7 needed for the program. At about 15 seats per extra room (p.6), capacity is ~440-455, so the 487 peak is ~107-111%.

Campus Readiness Profile

Sitton

Readiness Status: Ready/ Minor Adjustments (3)

Capacity at a Glance

FUNCTIONAL CAPACITY (1)
419 students

PEAK ENROLLMENT
465 students In 2029 (2)

LARGEST HISTORIC ENROLLMENT
449 students in 1996-1997

CLASSROOM USE
5 SPED classrooms
21 classrooms

Planned Future Investments
PCEF Schoolyard Upgrade

Readiness for Additional Students

- Urgent improvement:
  - Nutrition Services kitchen additions (see below):
    - $80,100 - completed by Summer 2027
- Needed improvement that does not affect school readiness: None
- Accessibility: 26 Accessible classrooms.
  - Full access to building.

Safety & Security

- Fencing/gates

Nutrition Services

- Double ovens, warming cabinet, dishwasher ($80,100)

Transportation

- City review and expansion required. Space available. No notable issues.

Special Education

- Inclusive School Community
- 4 Learning Center Teachers
- 1 Sensory/Regulation Space
- 5 Classrooms Total

-5

1. Was 496 in April.
2. 465 / 419 = 111%.
3. Over capacity at peak, yet rated "Ready." George at 107% is "Not Yet Ready."

Campus Readiness Profile

Vestal

Readiness Status: Ready/ Minor Adjustments

Capacity at a Glance

FUNCTIONAL CAPACITY 1
516 students

PEAK ENROLLMENT
507 students In 2027

LARGEST HISTORIC ENROLLMENT 2
451 students in 2010-2011

CLASSROOM USE

4 SPED classrooms
28 classrooms

Planned Future Investments

None

Readiness for Additional Students

- Urgent improvement:
  - Nutrition Services kitchen additions (see below):
    - $27,000 - completed by Summer 2027
- Needed improvement that does not affect school readiness: None
- Accessibility: 18 Accessible classrooms.
  - First floor accessible
  - Does not have an elevator

Safety & Security

- Fencing
- Additional cameras to cover blind spots

Nutrition Services

- Double ovens ($27,000), would need additional tables

Transportation

- City review and expansion required. On property adjustments required and able to accommodate.

Special Education

- 1.5 Learning Center Teachers
- 2 ISC classrooms
- 4 Classrooms Total

-2

1 Was 465 in April. At 465 the SO7 peak is 109%.

2 Peak SO7 is above the most Vestal has ever had (451).

Campus Readiness Profile

Whitman

Readiness Status: Ready/ Minor Adjustments (2)

Capacity at a Glance

FUNCTIONAL CAPACITY
416 students

PEAK ENROLLMENT
466 students In 2032 (1)

LARGEST HISTORIC ENROLLMENT
475 students in 2001-02

CLASSROOM USE (3)
1 SPED classrooms
23 classrooms

Planned Future Investments
None

Readiness for Additional Students

- Urgent improvement:
  - Nutrition Services kitchen additions (see below):
    - $3,100 - completed by Summer 2027
- Needed improvement that does not affect school readiness: None
- Accessibility: 24 Accessible classrooms.
  - Accessible route to front door is indirect.

Safety & Security
- Fencing
- Additional access controlled doors
- Additional cameras to address blind spots

Nutrition Services
- Warming Cabinet ($3,100)

Transportation
- City review and expansion required. On property adjustments required and able to accommodate.

Special Education
- Inclusive School Community
- 4 Learning Center Teachers when combined with Woodmere
- 1 Regulation/Sens[illegible] Space
- 4-5 Classrooms Total (4)

-5

1. 466 / 416 = 112%.
2. Over capacity at peak, yet rated "Ready."
3. 1 special-ed room counted...
4. ...4-5 needed with Woodmere. Capacity would drop further.

District-Wide ADA Accessibility

- Title II of the Americans with Disabilities Act (ADA) requires state and local governments, including public school districts, to give people with disabilities an equal opportunity to benefit from all of their programs, services, and activities.
- School districts must provide program access by ensuring that students with disabilities are not excluded from programs because existing buildings or facilities are inaccessible to them.
- When school districts build or alter facilities, they must make them accessible to people with disabilities, following ADA standards.
- All PPS campuses are ADA accessible to the main floor. 1

-2

1 Main floor only. Hosford's basement classrooms are "inaccessible or difficult" (p.20); Gray's route is "indirect and difficult" (p.18); many receiving schools have no elevator.

Seismic

Scenario A

Rose City Park & Beach seismic $ - reallocated to:

- Abernethy: (upgrade load bearing URM wall in gym)
- Arleta: (upgrade Building Part A)
- Brentwood: (upgrade Building Part D)
- Duniway: (upgrade URM in D and improve cafeteria)
- Hosford: (upgrade Cafeteria/Building Part B)
- Markham: (upgrade URM walls)
- Rigler: (upgrade URM walls)
- Rieke: (upgrade Building Parts A, B and C)
- Whitman: (upgrade Building Part A)

Scenario B

Beach seismic $ - reallocated to:

- Duniway: (upgrade URM in D and improve cafeteria)
- Rieke: (upgrade Building Parts A, B and C)

*Applying for SRGP grant for Rieke (Building Parts B and C)

-3

Rieke gets seismic money in both scenarios but has no readiness profile, even though it takes 30% of Maplewood plus the Stephens Creek Crossing area and has the highest seismic score of any receiving school (9.6).

Seismic

	District Seismic Risk Score and Projections[1,2]			
	2025 Values[3]	Status Quo Values[4]	Scenario A Values[5]	Scenario B Values[6]
PK-8 Ages	6.59	6.36	6.19	6.21
Full District	5.45	5.30	5.04	5.09

Both scenarios show a ***reduction*** in district wide seismic risk.

[1] District Seismic Risk Score is the average of each building part's seismic risk score, weighted by floor area. Larger buildings count for more.

[2] Buildings at schools not assessed in 2024-25 (new builds or recent retrofits) were assigned placeholder scores: new build=1.5; retrofit RC IV=3; retrofit RC III=4; (RC = risk category). This ensures the District Score does not exclude lower scoring buildings.

[3] Per the 2025 Seismic Risk Assessment

[4] Include score updates for all selected 2025 Bond retrofit projects

[5] Include score updates for 2025 Bond retrofit projects (excluding RCP and Beach) and include proposed projects. Removes closed schools.

[6] Include score updates for 2025 Bond retrofit projects (excluding Beach) and include proposed projects. Removes closed schools.

Seismic

Scenario Impacts on Enrollment at Campuses with Building Parts Rated 9.0+ or URM		Student Count				Normalized Student Count[1] (assumes 25-26 enrollment for consistent comparison)			
		Enrollment 25-26		Enrollment 31-32		Enrollment 25-26		Enrollment 31-32	
		2025 Values[2]	Status Quo[3]	Scenario A[4]	Scenario B[5,6]	2025 Values[2]	Status Quo[3]	Scenario A[4]	Scenario B[5,6]
	Total Enrollment	24,646	24,646	24,541	25,031	24,646	24,646	24,646	24,646
	Campus w/ bldg part > 9.0	11,175	8,249	7,981	8,414	11,175	8,249	8,015	8,285
	Campus w/ URM	7,845	4,837	2,718	3,981	7,845	4,837	2,730	3,920
Percent of total enrollment	Campus w/ bldg part > 9.0	45.3%	33.5%	32.5%	33.6%	45.3%	33.5%	32.5%	33.6%
	Campus w/ URM	31.8%	19.6%	11.1%	15.9%	31.8%	19.6%	11.1%	15.9%
Change from 2025 Values	Campus w/ bldg part > 9.0	-	-2,926	-3,194	-2,761	-	-2,926	-3,160	-2,890
	Campus w/ URM	-	-3,008	-5,127	-3,864	-	-3,008	-5,115	-3,925
Percent Change from 2025 Values	Campus w/ bldg part > 9.0	-	-26.2%	-28.6%	-24.7%	-	-26.2%	-28.3%	-25.9%
	Campus w/ URM	-	-38.3%	-65.4%	-49.3%	-	-38.3%	-65.2%	-50.0%

Both scenarios show a ***reduction*** in the proportion of students attending schools with building parts rated 9.0+ and schools with URM buildings.

[1] Normalized figures hold total enrollment at 2025-26 levels so the scenarios can be compared on a consistent basis. They are for comparison only, not forecasts of actual student counts or student moves.
[2] Per the 2025 Seismic Risk Assessment
[3] Include score updates for all selected 2025 Bond retrofit projects
[4] Include score updates for 2025 Bond retrofit projects (excluding RCP and Beach) and include proposed projects. Removes closed schools.
[5] Include score updates for 2025 Bond retrofit projects (excluding Beach) and include proposed projects. Removes closed schools.
[5] Scenario B enrollment figures were estimated by extrapolating from the Scenario A figures and may be overstated. Treat them as preliminary estimates, not forecasts.

-10

1. Normalized: Scenario B 33.6% vs. status quo 33.5%. B is slightly WORSE than doing nothing.
2. Scenario A improves on doing nothing by 1.0 point (234 students).
3. The "reduction" is measured from 2025. Most of it (-2,926 students) comes from bond retrofits that happen under the status quo too.
4. Left table: Scenario B total (25,031) is larger than status quo (24,646). It compares 2025-26 with 2031-32 enrollment.
5. URM gain counts the p.31 "proposed projects" as done: URM work at Abernethy, Duniway, Markham, Rigler, Rieke (~2,300 students under A). Leave them out and A has about as many students on URM campuses as doing nothing (~5,000 vs 4,837).

Next Steps

- Collaborate with Principals and school teams to refine school-specific implementation plans aligned to each school's transition year.
- Confirm all receiving-school space plans and priority upgrades.
- Finalize transportation, arrival/dismissal, and Safe Routes to School improvements.
- Coordinate moving schedules, technology, equipment, and classroom setup.
- Share school-specific milestones with families and staff, and monitor readiness through opening.

RIGHTSIZE. RIGHT SUPPORT.
RIGHT for STUDENTS.

Questions and Discussion